

BRUHATH BANGALORE MAHANAGARA PALIKE

Name of work : - Improvements to roads and drains at Kodigehalli village from 1st to 3rd cross and other roads in ward No. 08, Kodigehalli

Agency: Technical Manager M/s KRIDL

Schedule B

Item No	Approved Quantity	Description of Item of Work	Unit	Approved Rates of M/s KRIDL	
				Rate in Figures	Rate in Words
1	253.87	Removing and refixing stone slabs of drains and pointing in CM (1:3)	Sqm	111.30	Rupees One Hundred Eleven And Paise Thirty Only
2	602.91	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	220.40	Rupees Two Hundred Twenty And Paise Forty Only
3	78.47	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	5505.64	Rupees Five Thousand Five Hundred Five And Paise Sixty Four Only
4	201.33	KSRB 4-6.1: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	273.48	Rupees Two Hundred Seventy Three And Paise Forty Eight Only
5	1610.64	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surfaces such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No.KBS 4.6.2 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	379.48	Rupees Three Hundred Seventy Nine And Paise Forty Eight Only
6	214.76	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggretes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6	Sqm	5998.54	Rupees Five Thousand Nine Hundred Ninety Eight And Paise Fifty Four Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-52

Item No	Approved Quantity	Description of Item of Work	Unit	Approved Rates of M/s KRIDL	
				Rate in Figures	Rate in Words
7	12.75	KSRB - 4.9.2: Providing TMT steel Fe500 reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebtrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three And Paise Ninety Six Only
8	7.34	KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortar 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing completeas per specification and direction of the engineer-in-charge	Sqm	4871.76	Rupees Four Thousand Eight Hundred Seventy One And Paise Seventy Six Only
9	1.84	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specification and direction of the engineer-in-charge	Sqm	5747.32	Rupees Five Thousand Seven Hundred Forty Seven And Paise Thirty Two Only
10	289.28	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate) with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	2111.00	Rupees Two Thousand One Hundred Eleven Only
11	12.24	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	5111.00	Rupees Five Thousand One Hundred Eleven Only
		GST @12%		507166.00	Rupees Five Lakh(s) Seven Thousand One Hundred Sixty Six Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

H.V. Y
Executive Engineer 13/12
Project Division
Yelahanka Zone
BBMP, Bangalore-92